BCCA PROGRAM DELIVERY INC.

#4 – 10145 Dallas Drive, Kamloops, BC V2C 6T4
Telephone (250) 573-3611 Fax (250) 573-5155

SCHEDULE 7
WORKS/SERVICES SCHEDULE

CONTRACT IDENTIFICATION NUMBER
BCCA PDI: _____

The contractor shall:

Construct approximately _____ meters of 4 Strand Barbed Wire Fence to include and meet the following conditions:

DISPOSAL OF MATERIAL:

1. The contractor agrees to dispose of dismantled fence material at an approved and designated site.

2. The contractor agrees to adhere to the Forestry Practices Code with respect to all work along the agreed upon fence line.

ADHERENCE TO FENCING STANDARDS:

1. The contractor agrees that the MFLNRORD Four Strand Barbed Wire Fence Specifications will be followed (Schedule 8).

2. The contractor will discuss and agree upon any variances with BCCA PDI and MFLNRORD standards with the designated representative of BCCA PDI, i.e., the Quality Assurance Representative assigned to this contract.

INCIDENTALS:

1. Unless stated otherwise, all incidentals to the project are included and must meet or exceed the attached BCCA PDI and MFLNRORD standards. The Quality Assurance Representative must approve incidentals.

RE-SEEDING:

1. The contractor agrees to accept responsibility for re-seeding along all disturbed soils and will use seed material approved by the BCCA PDI Representative.

MATERIALS:

1. All materials are the responsibility of the contractor and must meet material specifications, Including **Class 3** barbed wire. Materials are to be transported at the contractor's expense to the job site.

RIGHT OF WAY

1. The contractor agrees to construct the new fence along the existing fence right-of-way allowing for realignment, unless otherwise approved by the BCCA PDI Representative. No debris or slash debris to be left on the cleared right of way.

QUALITY ASSURANCE

1. For the purposes of quality control:
    a. The contractor agrees to a quality assurance review at 400 m of fence construction and again at the completion of the project. It is also understood that the Quality Assurance Representative may inspect fence at any point in time during construction.
    b. The contractor agrees that any deficiencies noted in writing, during inspections, have to be resolved prior to completion. Not resolving any and all deficiencies in a manner approved by the Quality Assurance Representative may jeopardize or terminate the contractor's eligibility as a Pre-Qualified Fence Contractor with BCCA PDI.

Pre-Qualified Contractors